

# Stormwater Brick® 4" x 8"

Permeable Interlocking Concrete Pavingstones

Cumberland Blend

 **Genest** 1-800-649-4773  
[www.GenestConcrete.com](http://www.GenestConcrete.com)

# Stormwater Brick®

## 4" x 8"

The Stormwater Brick used as part of a permeable pavement system is an excellent way to control runoff water. The aggregate base used in the system helps to filter and reduce pollutants. The ground water is recharged because the water is not running off the pavement. Not only does it collect and properly handle storm water, but provides a functional and attractive paving solution.

### Packaging

- 78.24 sq. ft. per pallet
- 4.5 pieces per sq. ft.



**4" x 8" x 3 1/8"**  
100 mm x 200 mm x 80 mm



**4" x 4" x 3 1/8"**  
100 mm x 100 mm x 80 mm



**Stormwater Brick® 4" x 8"**  
Cumberland Blend (shown wet)

### Standard Colors




**Granite Blend**



**Cumberland Blend**

## ICPI\* Sample System Design



- Stormwater Brick®
- Bedding and Joint Material - *Typically #8 Stone*
- Open-Graded Base - *Typically #57 Stone*
- Open-Graded Sub-Base - *Typically #2 Stone*
- Under drain
- Optional Geotextile
- Uncompacted Soil

General specifications meet or exceed ASTM C-936  
Compressive strength: 8,000 PSI minimum  
Maximum water absorption: 5%  
Equals or exceeds freeze-thaw resistance

**Design and Specification Aids:** Stormwater Brick Installation and guide specifications are available at [www.genestconcrete.com](http://www.genestconcrete.com). Or you can speak directly with our sales department at **800-649-4773**

 **Genest**  
**1-800-649-4773**  
**www.GenestConcrete.com**

\*Interlocking Concrete Paver Institute - [www.icpi.org](http://www.icpi.org)